



PAT Testing Transmille 3200/2100

Supply Connection

The 3200/2100 needs to be connected to a line supply without RCD protection unless the unit has had the Earth-Neutral option installed.

PAT Testing 3200/2100

Note that due to the nature of the tests performed by the 3200/2100 the unit will fail the insulation test performed by a PAT tester

It is only the Visual and Earth Bond tests that can be performed